



## **ADDENDUM # 1**

June 5, 2026

### **Questions concerning Tender: PLANE AND PAVE VARIOUS AREAS WITHIN TOWN BOUNDARY TOWN OF STEWIACKE STEW-2026-03**

#### **Area 1 – Kitchener St.**

**Question:** Is the entire surface being planed? Or just keys at the limits for tie ins

**Answer:** Just keyed at each end.

**Question:** Are asphalt/gravel driveway tie ins considered incidental to the noted work?

**Answer:** The contractor should tie in the new asphalt to gravel driveways and asphalt driveways,

**Question:** With the sidewalk being inconsistent in elevations, broken edges, some pieces are asphalt and some are concrete, can you elaborate on the expectation for matching into it?

**Answer:** Match with asphalt

**Question:** Some driveways have concrete pads into the road surface, what is the expectations at these areas?

**Answer:** Tie in with asphalt

**Question:** What is to be done with the drain that goes from the road under the sidewalk between civic 135 & 129?

**Answer:** Keep it clear and blend to the drain.

**Question:** Who is responsible for line paint reinstatement?

**Answer:** Please include this in your price.

---

295 George Street, P.O. Box 8  
Stewiacke, NS, B0N 2J0  
Telephone: 902-639-2231  
Email: [procurement@stewiacke.net](mailto:procurement@stewiacke.net)



**Area 2 - Asquith**

**Question:** Is the entire surface being Planed? Or just keys around the perimeter for tie ins.

**Answer:** Yes all area to be planed.

**Question:** There is also a concrete apron extending into this area, what is the expectation here?

**Answer:** blend with asphalt.

**Question:** Who is responsible for coordination/costs associated with CN Rail while working in proximity or their right of way?

**Answer:** The contractor is to coordinate with CN rail.

**Question:** Who is responsible for line paint reinstatement.

**Answer:** Please include this in your price.

**Note: Please include in your price raising all hardware (Manhole / water main covers etc.)**

